

VILLAGE OF WESTFIELD CENTER

WESTFIELD CENTER, OHIO

SPECIFICATIONS FOR COMMUNITY PARK SITE IMPROVEMENTS PROJECT

ADDENDUM NO. 1

August 10, 2010

All prospective bidders are hereby notified that this addendum forms a part of the contract documents and modifies the original bidding documents dated July 2010. Acknowledge receipt of this addendum in the space provided in the bid proposal section of the specifications. Failure to do so may subject the bidder to disqualification.

PREPARED BY:

**GGJ, INC.
35585 Curtis Blvd., Suite C
Eastlake, Ohio 44095
(440) 953-1567 (voice)
(440) 953-0580 (fax)**

****THIS ADDENDUM IS BEING TRANSMITTED VIA
FAX ONLY. NO "HARD COPY" WILL BE SENT.****

**Please acknowledge receipt by signing below
and faxing back this cover sheet only ASAP
to (440)953-0580.**

COMPANY _____

NAME _____

DATE _____

CONTRACT SPECIFICATIONS

Specifications

1. Section 00300 – Bid Proposal Form

REPLACE Entire Section.

2. Section 02830 – Galvanized Fence & Gates

DELETE 3.02, E.

“E. Drive Anchor line posts: With protective cap, drive post 36” (914 mm) into ground. Slightly below ground level install drive anchor shoe fitting. Install 2 diagonal drive anchors and tighten in the shoe. “

ADD 3.02, E.

“E. Concrete set line posts: Drill holes in firm, undisturbed or compacted soil. Holes shall have diameter 4 times greater than outside dimension of post, and depths approximately 6”(152 mm) deeper than post bottom. Excavate deeper as required for adequate support in soft and loose soils, and for posts with heavy lateral loads. Set post bottom 36” (914 mm) below surface when in firm, undisturbed soil. Place concrete around posts in a continuous pour. Trowel finish around post. Slope to direct water away from posts.”

Drawings

1. Sheet 2 of 12 – Overall Site Plan

DELETE Note “12” HDPE and inlets. See Cross Section for information”

ADD Note “15” HDPE and inlets. See Cross Section for information”

(See attached sketch.)

2. Sheet 5 of 12 – Field Details

DELETE Chain Link Fence Detail Note “Chain link wire fabric, top & bottom edges knuckle. All Field #1 perimeter fence to be final coated. Color: Black”

ADD Chain Link Fence Detail Note “Chain link wire fabric, top & bottom edges knuckle. All fence fabric shall be galvanized per specifications.”

3. Sheet 10 of 12 – Trail Cross Sections

REVISE Cross Section 47+50 as indicated. (See attached sketch).

VILLAGE OF WESTFIELD CENTER, OHIO
COMMUNITY PARK SITE IMPROVEMENTS PROJECT

BASIS OF PAYMENT

GENERAL: Payment for the work Items shall be at the total unit or lump sum price Bid for each unit of work completed and accepted in accordance with the Contract Documents.

The latest "State of Ohio, Department of Transportation, Construction and Material Specifications" manual shall govern the material and procedures used in this project, if not otherwise specified in the project Specifications or noted on the Drawings.

PRICES TO INCLUDE: For each Bid Item, the total unit price or lump sum price Bid shall be considered full compensation for the completed and accepted work, and shall include all labor, materials, tools, equipment and transportation needed to perform the work in accordance with the Contract Documents so as to provide a complete and properly functional system. The General Contractor shall be responsible for reviewing the contents and conditions of all Contract Documents as they may relate to the work under this Contract and comply with the requirement thereof.

ITEM 1 - BONDS AND INSURANCE

A. Payment:

1. The lump sum amount stated in the Bid Schedule for bonds and insurance shall include all bonds and insurance required to be in force at the commencement of the work. Successful bidder will be required to provide receipts verifying the actual costs of this item when known.
2. Subsequent expenses for bonds and insurance as may be necessary throughout the contract period for changes to the contract or for other occurrences, shall not be a part of this item.
3. Fees for bonds and insurance due to changes in the work shall be respectively a part of the cost of that work.

ITEM 2 - MOBILIZATION

- A. Work included: As described in Section 00800 Supplementary Conditions SC-22 and other work incidental to this Item.
- B. Payment: Lump Sum price with payments as specified in Section 00800 Supplementary Conditions SC-22.

ITEM 3 – CONSTRUCTION LAYOUT STAKES (ODOT ITEM 623)

- A. Description: This work in this Item shall consist of providing all construction stakes required to complete the work as shown in the Drawings and/or specified in the Contract Documents.
- B. Payment: The Lump Sum Price bid for this Item shall include providing all construction stakes required to complete the work as shown in the Drawings and/or specified in the Contract Documents.

ITEM 4 – SELECTIVE CLEARING & GRUBBING

- A. Description: The work in this Item consist of the removal and disposal of existing trees and vegetation as shown on the Drawings and/or Specifications and as follows:
1. All removed material shall be disposed of by the Contractor at his own expense.

2. It is the Contractor's responsibility to field verify the trees that remain within the construction limits. The drawings have been updated from the original survey to represent the trees that appear to have been removed. All trees shown to be removed, as well as those that are shown on the plans as being removed (but are verified to exist), shall be included in this bid item.
- B. Payment: The Lump Sum Price bid stipulated for removal of this item shall be for the total cost included for labor, equipment, root removal, restoration to effected areas, and disposal of same by the contractor.

ITEM 5 – TREES, STUMPS AND ROOTS REMOVED

- A. Description: The work in this Item consist of the removal and disposal of existing tree and shrub roots as shown on the Drawings and/or Specifications and as follows:
1. All removed material shall be disposed of by the Contractor at his own expense.
 2. It is the Contractor's responsibility to field verify the trees that remain within the construction limits. The drawings have been updated from the original survey to represent the trees that appear to have been removed to allow for the utility relocation. All trees shown to be removed, as well as those that are shown on the plans as being removed (but are verified to exist), shall be included in this bid item.
- B. Payment: The Lump Sum Price bid stipulated for removal of this item shall be for the total cost included for labor, equipment, stump removal, restoration to effected areas, and disposal of same by the contractor.

ITEM 6 - EXCAVATION INCLUDING EMBANKMENT

- A. Description: The work in this Item shall consist of the removal and disposal of existing material, including existing topsoil, as necessary, to reach the bottom of the sub-base of the proposed pavement. This item also includes the use of acceptable excavated material to be used for embankment purposes, replacement of topsoil, fine grading of site and maintenance of traffic as shown on the Drawings and/or Specifications.
- B. Payment: The unit price stipulated for this Item– Excavation Including Embankment Construction including removal and disposal of existing material, and providing as-built information will be lump sum for all work involved.

ITEM 7 - 1-1/2" ASPHALT CONCRETE (AC-20, SURFACE COURSE TYPE 1)

- A. Description: The work in this Item shall consist of constructing a surface course of aggregate and asphalt cement mixed in a central plant and spread on a prepared surface in accordance with the Drawings and/or Specification.
- B. Payment: The unit price stipulated per cubic yard of this Item – Asphalt Concrete, shall be full compensation for the actual number of cubic yards installed complete and in place, including labor, materials and equipment.

ITEM 8- 1-1/2"" ASPHALT CONCRETE (AC-20, LEVELING COURSE TYPE 2)

- A. Description: The work in this Item shall consist of constructing a leveling course of aggregate and asphalt cement mixed in a central plant and spread on a prepared surface in accordance with the Drawings and/or Specification.
- B. Payment: The unit price stipulated per cubic yard of this Item – Asphalt Concrete, shall be full compensation for the actual number of cubic yards installed complete and in place, including labor, materials and equipment.

ITEM 9 - TACK COAT .05 GAL./S.Y.

- A. Description: The work in this Item shall consist of preparing and treating a paved surface with bituminous material and will be measured by the gallon actually installed under this item.
- B. Payment: The unit price stipulated per gallon of this Item – Tack Coat as shown on the Drawings and/or Specifications including labor, materials and equipment.

ITEM 10 - PRIME COAT 0.35 GAL./S.Y.

- A. Description: The work in this Item shall consist of preparing and treating a paved surface with bituminous material and will be measured by the gallon actually installed under this item.
- B. Payment: The unit price stipulated per gallon of This Item – Prime Coat as shown on the Drawings and/or Specifications including labor, materials and equipment.

ITEM 11 - 6" AGGREGATE BASE (LIMESTONE AGGREGATE)

- A. Description: The work in this Item shall consist of the furnishing, placing and compacting one or more courses of aggregate, including furnishing and incorporating all water required for compacting on a prepared surface, and in reasonably close conformity to the lines, grades and typical cross sections shown on the Drawings and/or Specifications.
- B. Payment: The unit price stipulated to be paid per cubic yard of aggregate base work performed and measured for payment purposes shall be full compensation for the actual number of cubic yards installed complete and in place, including labor, materials and equipment.

ITEM 12 – SUBGRADE COMPACTION

- A. Description: The work in this Item shall consist of the preparation of the sub-grade where pavement is to be placed. Including the testing of the stability and uniformity of compaction as well as proof rolling of the same.
- B. Payment: The unit price stipulated shall be full compensation for each square yard of Sub-grade Compaction as measured under the proposed pavement and shall include Proof Rolling.

ITEM 13 – 4" STABILIZED CRUSHED AGGREGATE (LIMESTONE AGGREGATE) (ODOT ITEM 411)

- A. Description: The work in this Item shall consist of the furnishing, placing and compacting one or more courses of aggregate, including furnishing and incorporating all water required for compacting on a prepared surface, and in reasonably close conformity to the lines, grades and typical cross sections shown on the Drawings and/or Specifications.
- B. Payment: The unit price stipulated to be paid per cubic yard of stabilized crushed aggregate work performed and measured for payment purposes shall be full compensation for the actual number of cubic yards installed complete and in place, including labor, materials and equipment to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 14 – AGGREGATE DRAIN

- A. Description: This work in this Item shall consist of the placement of aggregate drains as shown on the plans and specification and shall include excavation and bedding.
- B. Payment: The unit price stipulated to be paid for each cubic yard of aggregate drain, shall be full compensation for the actual number of cubic yard of aggregate drain furnished and installed including labor, materials and equipment.

ITEM 15 – ADS Drains

- A. Description: The work in this Item shall consist of the construction of ADS storm inlets of the type and sizes shown on the Drawings and /or Specifications.
- B. Payment: The unit price for each ADS storm inlet shall be full compensation for the storm inlet, furnished, installed, and connected in accordance with the Drawings and Specifications including excavation, backfill, labor material, frame and grates, equipment, and restoration of all disturbed areas and utilities, and all other appurtenances for the work shown on the Drawings and/or specified in the Construction Documents for a complete and ready-for-use installation.

ITEM 16 – 8" CONDUIT, (HDPE)

- A. Description: The work in this Item shall consist of the construction of 6" Conduit, (HDPE) and shall conform to the Drawings and /or Specifications. Deductions shall be made for manholes or catch basins in the line of the pipe. Refer to latest revision of Ohio Department of Transportation, Construction and Material Specifications and all related supplemental information.
- B. Payment: The unit price stated on the Bid Schedule shall be compensation for each lineal foot of pipe installed including all fittings and plugs measured for payment. The price shall include furnishing labor, backfill, compaction, laying, sheeting, shoring, inspection, testing of pipe and fittings, removal of existing sewers, restoring all disturbed areas and utilities, and all appurtenances to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 17 – 12" CONDUIT, (HDPE)

- A. Description: The work in this Item shall consist of the construction of 12" Conduit, (HDPE) and shall conform to the Drawings and /or Specifications. Deductions shall be made for manholes or catch basins in the line of the pipe. Refer to latest revision of Ohio Department of Transportation, Construction and Material Specifications and all related supplemental information.
- B. Payment: The unit price stated on the Bid Schedule shall be compensation for each lineal foot of pipe installed including all fittings and plugs measured for payment. The price shall include furnishing labor, backfill, compaction, laying, sheeting, shoring, inspection, testing of pipe and fittings, removal of existing sewers, restoring all disturbed areas and utilities, and all appurtenances to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 18 – 18" CONDUIT, (HDPE)

- A. Description: The work in this Item shall consist of the construction of 18" Conduit, (HDPE) and shall conform to the Drawings and /or Specifications. Deductions shall be made for manholes or catch basins in the line of the pipe. Refer to latest revision of Ohio Department of Transportation, Construction and Material Specifications and all related supplemental information.
- B. Payment: The unit price stated on the Bid Schedule shall be compensation for each lineal foot of pipe installed including all fittings and plugs measured for payment. The price shall include furnishing labor, compaction, laying, sheeting, shoring, inspection, testing of pipe and fittings, removal of existing sewers, restoring all disturbed areas and utilities, and all appurtenances to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 19 – 12" CONDUIT, TYPE B, 706.02 (ODOT ITEM 603)

- A. Description: The work in this Item shall consist of the construction of 12" Conduit, Type B (706.02) and shall conform to the Drawings and /or Specifications. Deductions shall be made for manholes or catch basins in the line of the pipe. Refer to latest revision of Ohio Department of Transportation, Construction and Material Specifications and all related supplemental information.
- B. Payment: The unit price stated on the Bid Schedule shall be compensation for each lineal foot of pipe installed including all fittings and plugs measured for payment. The price shall include furnishing labor, backfill, compaction, laying, sheeting, shoring, inspection, testing of pipe and fittings, removal of existing sewers, restoring all disturbed areas and utilities, and all appurtenances to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 20 – 12" ODOT HEADWALL- HW 2.2

- A. Measurement: Shall be made on a unit basis for each headwall actually installed under this item.
- B. Payment: The unit price stipulated to be paid for outfall headwall shall be full compensation for each headwall installed including furnishing, excavation, backfill, compacting, concrete work, pipe anchoring, rip-rap, and other items as per headwall detail.

ITEM 21 – 12" ODOT HEADWALL- HW 2.1

- A. Measurement: Shall be made on a unit basis for each headwall actually installed under this item.
- B. Payment: The unit price stipulated to be paid for outfall headwall shall be full compensation for each headwall installed including furnishing, excavation, backfill, compacting, concrete work, pipe anchoring, rip-rap, and other items as per headwall detail.

ITEM 22 – 18" ODOT HEADWALL- HW 2.1

- A. Measurement: Shall be made on a unit basis for each headwall actually installed under this item.
- B. Payment: The unit price stipulated to be paid for outfall headwall shall be full compensation for each headwall installed including furnishing, excavation, backfill, compacting, concrete work, pipe anchoring, rip-rap, and other items as per headwall detail.

ITEM 23 – WOOD BOARDWALK

- A. Description: The work in this Item shall consist of the furnishing, and installation of wood boardwalk as shown on the Drawings and/or Specifications.
- B. Payment: The unit price stipulated to be paid per lump sum for payment purposes shall be full compensation for the wood boardwalk installed complete and in place, including labor, materials and equipment to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 24 – BOARDWALK POST BASES

- A. Description: The work in this Item shall consist of the furnishing, and installation of concrete boardwalk post bases as shown on the Drawings and/or Specifications.
- B. Payment: The unit price stipulated to be paid per each for payment purposes shall be full compensation for the concrete boardwalk post bases installed complete and in place, including labor, materials and equipment to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 25 – BOARDWALK TRANSITION FOOTING

- A. Description: The work in this Item shall consist of the furnishing, and installation of concrete boardwalk transition footing as shown on the Drawings and/or Specifications.
- B. Payment: The unit price stipulated to be paid per each for payment purposes shall be full compensation for the concrete boardwalk transition footing installed complete and in place, including labor, materials and equipment to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 26 – FIELD #1 FENCING, GATES & BACKSTOP

- A. Description: The work in this Item shall consist of providing and installing chainlink fences, gates, aggregate bleacher areas, and backstop at locations shown on the Drawings and /or Specifications and shall include anchors, bedding, restoration and backfill.
- B. Payment: The lump sum unit price for the field fencing, gates, and backstop shall be full compensation for the equipment, furnished, installed, and connected in accordance with the Drawings and Specifications including excavation, backfill, labor material, equipment, and restoration.

ITEM 27 – FIELD #2 FENCING, GATES & BACKSTOP

- A. Description: The work in this Item shall consist of providing and installing chainlink fences, gates, aggregate bleacher areas, and backstop at locations shown on the Drawings and /or Specifications and shall include anchors, bedding, restoration and backfill.

- B. Payment: The lump sum unit price for the field fencing, gates, and backstop shall be full compensation for the equipment, furnished, installed, and connected in accordance with the Drawings and Specifications including excavation, backfill, labor material, equipment, and restoration.

ITEM 28 – FIELD #3 FENCING, GATES & BACKSTOP

- A. Description: The work in this Item shall consist of providing and installing chainlink fences, gates, aggregate bleacher areas, and backstop at locations shown on the Drawings and /or Specifications and shall include anchors, bedding, restoration and backfill.
- B. Payment: The lump sum unit price for the field fencing, gates, and backstop shall be full compensation for the equipment, furnished, installed, and connected in accordance with the Drawings and Specifications including excavation, backfill, labor material, equipment, and restoration.

ITEM 29 – FIELD #4 BACKSTOP

- A. Description: The work in this Item shall consist of providing and installing the chainlink backstop at location shown on the Drawings and /or Specifications and shall include anchors, bedding, restoration and backfill.
- B. Payment: The lump sum unit price for the field backstop shall be full compensation for the equipment, furnished, installed, and connected in accordance with the Drawings and Specifications including excavation, backfill, labor material, equipment, and restoration.

ITEM 30 – FIELD DUGOUTS

- A. Description: The work in this Item shall consist of providing and installing the field dugouts at locations shown on the Drawings and /or Specifications and shall include anchors, bedding, restoration and backfill.
- B. Payment: The unit price for each the field dugout shall be full compensation for the equipment, furnished, installed, and connected in accordance with the Drawings and Specifications including excavation, backfill, labor material, equipment, and restoration.

ITEM 31 – FIELD EQUIPMENT

- A. Description: The work in this Item shall consist of providing and installing base pads, pitchers rubber, and home plate, foul poles with ground sleeves, benches, and fence guards at locations shown on the Drawings and /or Specifications and shall include anchors, bedding, and backfill.
- B. Payment: The lump sum unit price for the field equipment shall be full compensation for the equipment, furnished, installed, and connected in accordance with the Drawings and Specifications including excavation, backfill, labor material, equipment, and restoration.

ITEM 32 – FLAGPOLE INSTALLATION

- A. Description: The work in this Item shall consist of the installation of the flagpole provided by Owner and shall conform to the Drawings and /or Specifications.
- B. Payment: The unit price stated on the Bid Schedule shall be compensation for the flagpole installed including all fittings, and concrete base measured for payment. The price shall include furnishing labor, backfill, compaction, restoring all disturbed areas, and all appurtenances to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 33 – TUBULAR STEEL GATE

- A. Description: The work in this Item shall consist of providing and installing the tubular steel gates at locations shown on the Drawings and /or Specifications and shall include foundation, bedding, restoration and backfill.
- B. Payment: The unit price for each tubular steel gate shall be full compensation for the equipment, furnished, installed, and connected in accordance with the Drawings and Specifications including foundation, backfill, labor material, equipment, and restoration.

ITEM 34 – SEEDING & MULCHING

- A. Description: The quantity of each type of seeding and mulching: preparing topsoil, seeding and mulching will be measured for unit price payment purposes will be the number of square yards of seeding and mulching: topsoil, seeding and mulching acceptably placed and compacted when required per detail as specified over an area with the contract (pay) limits.
- B. Payment: The unit price stipulated to be paid per square yard of seeding and mulching: topsoil, seeding and mulching work performed and measured for payment purposes shall be full compensation for the actual number of square yards furnished and installed which is directly or indirectly caused by the installation of pavements, waterlines, sanitary sewers, storm sewers and relocation of utilities caused by this construction and other work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ALT. ITEM 36– INFIELD SOIL MIX (Fields #1, #2, & #3)

- A. Description: The work in this Item shall consist of the providing and installing infield soil mix at locations shown on the Drawings and /or Specifications and shall include grading, installation of material, and restoration.
- B. Payment: The unit price for the lump sum shall be full compensation for the materials, furnished, installed, and connected in accordance with the Drawings and Specifications including grading, labor, material, equipment, and restoration.

THIS PAGE INTENTIONALLY LEFT BLANK

PROPOSAL TO THE VILLAGE OF WESTFIELD CENTER, OHIO
COMMUNITY PARK SITE IMPROVEMENTS PROJECT

TO: MAYOR THOMAS HORWEDEL
VILLAGE OF WESTFIELD CENTER
6701 GREENWICH RD.
WESTFIELD CENTER, OHIO 44251

Gentlemen:

Proposal of _____(hereinafter called "BIDDER"), organized and existing under the laws of the State of Ohio doing business as _____.
To the VILLAGE OF WESTFIELD CENTER (hereinafter called "Owner").

In compliance with your Advertisement for Bids, BIDDER hereby proposes to perform all WORK for the construction of the COMMUNITY PARK SITE IMPROVEMENTS PROJECT in strict accordance with the CONTRACT DOCUMENTS, within the time set forth therein, and at the prices stated below.

By submitting this BID, the BIDDER, or in the case of a joint BID, each party thereto, certifies as to its own organization, that this BID has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this BID with any other BIDDER or with any competitor.

The undersigned have full knowledge of the project site, Drawings, and the conditions of the proposal. The undersigned also, hereby agrees to furnish all the services, labor, materials and equipment necessary to complete these projects according to the Drawings and Specifications and to accept as full compensation the lump sum or unit prices stated in the Bid Schedule for the work and for use when calculating the price of a deduction or an increase in quantities.

BIDDER hereby agrees to commence WORK under this Contract on or before a date to be specified in the NOTICE TO PROCEED and to fully complete the PROJECT within the period stipulated in the INSTRUCTIONS TO BIDDERS. BIDDER further agrees to pay as liquidated damages and that the CITY may retain from monies that are, or which may become due. The amount of such liquidated damages shall be as stipulated in the CONTRACT AGREEMENT FORM (Section 00500 herein).

* Insert "a corporation", "a partnership", or "an individual" as applicable.

The Bidder hereby acknowledges receipt of the following addenda:

<u>ADDENDUM NO.</u>	<u>DATE</u>
<hr/>	<hr/>
<hr/>	<hr/>
<hr/>	<hr/>

We further agree that the Owner may reject any or all bids.

SUBMITTED BY:

Firm, Corporation or Individual

Address

Telephone Number

Contractor License Number

Signature:

 Date:

NOTE: Evidence of authority to sign and the corporate seal must be affixed and attested by the Secretary.

COMPLETION DATE: 60 Calendar Days commencing on the date as shown on Notice to Proceed for Final Completion.

PROPOSAL TO THE VILLAGE OF WESTFIELD CENTER, OHIO
COMMUNITY PARK SITE PREPARATION PROJECT

BASE BID SCHEDULE

Bid Item	Item Description	Est. Qty.	Unit	Unit Price Material	Unit Price Labor	Total Unit Price	Total Price
General							
1	Bond & Insurance	1	Lump Sum				\$ -
2	Mobilization	1	Lump Sum				\$ -
3	Construction Staking	1	Lump Sum				\$ -
Clearing & Grubbing							
4	Clearing & Grubbing	1	Lump Sum				\$ -
5	Trees, Stumps and Roots Removed	1	Lump Sum				\$ -
Earthwork							
6	Excavation & Embankment	1250	CY				\$ -
Pavement							
7	Asphalt Surface Course (1.5")	165	CY				\$ -
8	Asphalt Intermediate Course (1.5")	174	CY				\$ -
9	Tack Coat (0.05 Gal./SY)	209	Gallon				\$ -
10	Prime Coat (0.35 Gal./SY)	1615	Gallon				\$ -
11	Aggregate Base (6" Limestone Aggregate)	769	CY				\$ -
12	Sub-grade Compaction	4613	SY				\$ -
13	Stabilized Crushed Aggregate (4")	116	CY				\$ -

Storm Sewers							
14	Aggregate Drains	5	CY				\$ -
15	ADS Drains	8	LF				\$ -
16	8" Conduit, (HDPE)	32	LF				\$ -
17	12" Conduit, (HDPE)	414	LF				\$ -
18	18" Conduit, (HDPE)	30	LF				\$ -
19	12" Conduit, Type B, 706.02 (RCP)	32	LF				\$ -
20	Half Height Headwall (HW-2.2) 12"	4	EA				\$ -
21	Half Height Headwall (HW-2.1) 12"	3	EA				\$ -
22	Half Height Headwall (HW-2.1) 18"	2	EA				\$ -
Sitework							
23	Wood Boardwalk	1	Lump Sum				\$ -
24	Boardwalk Post Bases	1	EA				\$ -
25	Boardwalk Transition Footing	2					\$ -
26	Field #1 Fencing, Gates & Backstop	1	Lump Sum				\$ -
27	Field #2 Fencing, Gates & Backstop	1	Lump Sum				\$ -
28	Field #3 Fencing, Gates & Backstop	1	Lump Sum				\$ -
29	Field #4 Backstop		EA				\$ -
30	Field Dugouts	6	EA				\$ -
Site Furnishings							
31	Field Equipment	1	Lump Sum				\$ -
32	Flagpole Installation	1	EA				\$ -

33	Tubular Steel Gate	1	EA				\$ -
Lawns							
34	Seeding and Mulching	16946	SY				\$ -
Sediment & Erosion Control							
35	Sediment & Erosion Control	1	Lump Sum				\$ -
TOTAL							\$ -

TOTAL AMOUNT OF PROJECT (IN FIGURES)

TOTAL AMOUNT OF PROJECT (IN WORDS)

ALTERNATE BID SCHEDULE

Bid Item	Item Description	Est. Qty.	Unit	Unit Price Material	Unit Price Labor	Total Unit Price	Total Price
36	Infield Soil Mix	1	Lump Sum				\$ -
TOTAL							\$ -

TOTAL AMOUNT ALTERNATE BID (IN FIGURES)

TOTAL AMOUNT OF ALTERNATE BID (IN WORDS)

THIS PAGE INTENTIONALLY LEFT BLANK