

CITY OF CLYDE

CLYDE, OHIO

SPECIFICATIONS FOR WEST MAPLE STREET SANITARY SEWER EXTENSION

ADDENDUM NO. 1

April 5, 2010

All prospective bidders are hereby notified that this addendum forms a part of the contract documents and modifies the original bidding documents dated April 2010. Acknowledge receipt of this addendum in the space provided in the bid proposal section of the specifications. Failure to do so may subject the bidder to disqualification.

PREPARED BY:

**GGJ, INC.
35585 Curtis Blvd., Unit C
Eastlake, Ohio 44095
(440) 953-1567 (voice)
(440) 953-0580 (fax)**

**Please acknowledge receipt by signing below and
faxing back this cover sheet only ASAP to
(440)953-0580.**

COMPANY _____

NAME _____

DATE _____

CONTRACT SPECIFICATIONS

Clarification

1. The connection at existing manhole #1 on West Maple Street will be on an existing stub and not into the manhole as listed on the drawings.
2. The type "C" pavement replacement detail is adequate as shown on the drawings and a concrete cap will not be required.
3. The section of sewer between MH #6 and MH #7 will be relocated further off of the edge of pavement. The grade will remain as shown but the new alignment will be 3 feet from the existing utility poles (2 poles located within this run of sewer). A new bit item will be included to account for holding of utility poles.
4. In general, the sewers placed parallel to Limerick and West Maple will require premium backfill.

Section 00300 – Bid Proposal Form

REPLACE Entire Section.

**CITY OF CLYDE
WEST MAPLE STREET SANITARY SEWER EXTENSION**

BASIS OF PAYMENT

GENERAL: Payment for the work Items shall be at the total unit or lump sum price Bid for each unit of work completed and accepted in accordance with the Contract Documents.

The latest "State of Ohio, Department of Transportation, Construction and Material Specifications" manual shall govern the material and procedures used in this project, if not otherwise specified in the project Specifications or noted on the Drawings.

PRICES TO INCLUDE: For each Bid Item, the total unit price or lump sum price Bid shall be considered full compensation for the completed and accepted work, and shall include all labor, materials, tools, equipment and transportation needed to perform the work in accordance with the Contract Documents so as to provide a complete and properly functional system. The General Contractor shall be responsible for reviewing the contents and conditions of all Contract Documents as they may relate to the work under this Contract and comply with the requirement thereof.

ITEM 1 - BONDS AND INSURANCE

A. Payment:

1. The lump sum amount stated in the Bid Schedule for bonds and insurance shall include all bonds and insurance required to be in force at the commencement of the work. Successful bidder will be required to provide receipts verifying the actual costs of this item when known.
2. Subsequent expenses for bonds and insurance as may be necessary throughout the contract period for changes to the contract or for other occurrences, shall not be a part of this item.
3. Fees for bonds and insurance due to changes in the work shall be respectively a part of the cost of that work.

ITEM 2 - MOBILIZATION

A. Work included: As described in Section 00800 Supplementary Conditions SC-22 and other work incidental to this Item.

B. Payment: Lump Sum price with payments as specified in Section 00800 Supplementary Conditions SC-22.

ITEM 3 – MAINTENANCE OF TRAFFIC

A. Description: The work in this Item shall consist of maintaining and protecting vehicular and pedestrian traffic at the work area while the contract is in force, in accordance with the latest Ohio Department of Transportation Construction and Material Specifications, including all current supplemental specifications and standard construction drawings and all specifications and drawings in these Contract Documents and in this contract book.

B. Payment: The Lump Sum Price bid for Item Maintaining Traffic shall include the cost of removal of conflicting pavement markings and placement of interim markings, maintaining the existing roadways in a safe condition for public use, providing flaggers and their equipment, furnishing and maintaining and subsequently removing temporary traffic control items as required by the plans and specifications.

ITEM 4 – 12" PVC SEWER, SDR 35

A. Description: The work in this Item shall consist of furnishing and installing PVC Sanitary Sewer Pipe as shown on the Drawings and/or specified. Measurements shall be made on a linear foot basis for the actual work

performed under this item, measured along the horizontal projection of the longitudinal axis of the pipe.

- B. Payment: The unit price stated on the Bid Schedule shall be compensation for each lineal foot of pipe installed including all fittings and plugs measured for payment. The price shall include furnishing labor, backfill, compaction, laying, sheeting, shoring, inspection, testing of pipe and fittings, restoring all disturbed areas and utilities, and all appurtenances to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for –use installation.

ITEM 5 – 12" PVC SEWER, SDR 35 (Premium Backfill)

- A. Description: The work in this Item shall consist of furnishing and installing PVC Sanitary Sewer Pipe as shown on the Drawings and/or specified. Measurements shall be made on a linear foot basis for the actual work performed under this item, measured along the horizontal projection of the longitudinal axis of the pipe.
- B. Payment: The unit price stated on the Bid Schedule shall be compensation for each lineal foot of pipe installed including all fittings and plugs measured for payment. The price shall include furnishing labor, backfill, compaction, laying, sheeting, shoring, inspection, testing of pipe and fittings, restoring all disturbed areas and utilities, and all appurtenances to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for –use installation.

ITEM 6 –SANITARY MANHOLE

- A. Description: This work consists of the construction of Manholes of the type and sizes shown on the Drawings and/or specified.
- B. Payment: For each Item - Manholes shall be as stated below:
 - 1. The unit price stated for each precast concrete manhole shall be full compensation for the manholes, furnished, installed, and connected in accordance with the Drawings and Specifications including excavation, backfill, labor, material, equipment, restoration, and removal of existing manholes.
 - 2. The unit price stated in the Bid Schedule shall include precast sections, waterproofing, manhole steps, grade adjusting, labor, construction, backfill, compaction, regular and drop manhole connections, frame and covers, restoration of all disturbed areas and utilities, and all other appurtenances for the work shown on the Drawings and/or specified in the Construction Documents for a complete and ready-for-use installation.

ITEM 7 – 6" PVC SEWER LATERAL (LONG)

- A. Description: This work shall consist of the construction of a 6" PVC SDR 35 Sewer Laterals per sewer customer within the Construction Area, as shown on the plans and specified herein. The sewer lateral per Customer consists of 1(one) sanitary lateral and 1 (one) Sanitary Cleanout.
- B. Payment: The unit price stipulated to be paid for each 6" PVC SDR 35, Sewer Lateral shall be full compensation for the total length of pipe installed including all fittings, plugs, and Cleanouts, and shall include furnishing labor, locating existing lateral, backfill, compaction, laying, sheeting, shoring, inspecting, testing of pipe and fittings, restoring all disturbed areas and utilities, and all appurtenances to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation of a sewer lateral system per customer.

ITEM 8 – 6" PVC SEWER LATERAL (SHORT)

- A. Description: This work shall consist of the construction of a 6" PVC SDR 35 Sewer Laterals per sewer customer within the Construction Area, as shown on the plans and specified herein. The sewer lateral per Customer consists of 1(one) sanitary lateral and 1 (one) Sanitary Cleanout.
- B. Payment: The unit price stipulated to be paid for each 6" PVC SDR 35, Sewer Lateral shall be full compensation for the total length of pipe installed including all fittings, plugs, and Cleanouts, and shall include furnishing labor, locating existing lateral, backfill, compaction, laying, sheeting, shoring, inspecting, testing of pipe and fittings, restoring all disturbed areas and utilities, and all appurtenances to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation of a sewer lateral system per customer.

ITEM 9 – ASPHALT DRIVE REMOVAL & REPLACEMENT

- A. Description: This work shall consist of removal and disposal of existing asphalt driveways and constructing an asphalt pavement as shown on the plans and specifications. The depth shall match the existing driveway sections that are being removed.
- B. Payment: The unit price stipulated shall be paid per square yard of this item, and shall be full compensation for removal, disposal, furnishing and placing all materials including labor, equipment, and saw cutting to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 10 – GRAVEL DRIVE REMOVAL & REPLACEMENT

- A. Description: This work shall consist of removal and disposal of existing gravel driveways and constructing a gravel pavement as shown on the plans and specifications. The depth shall match the existing driveway sections that are being removed.
- B. Payment: The unit price stipulated shall be paid per square yard of this item, and shall be full compensation for removal, disposal, furnishing and placing all materials including labor, equipment, and saw cutting to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 17 – TYPE “C” PAVEMENT REMOVAL & REPLACEMENT

- A. Description: The work in this Item shall consist of the full depth replacement of pavement in the areas shown on the Drawings, excluding pavement replacement covered in Bid Items 8 and 9. All replacement shall be in accordance with O.D.O.T. Items 301, 304, 403, 404, 407, 408, 409, 448, 452, & 702.
 - a. All removed material shall be disposed of by the Contractor at his own expense.
- B. Payment: The unit price stipulated to be paid for each square yard of pavement replacement shall be full compensation for the actual number of square yards, calculated from payment limits as called for in the contract drawings, completed in compliance with the contract drawings and specifications and accepted for payment purposes and shall include furnishing all labor, materials, tools, appliances and equipment necessary thereto and, in connection with same, restore all disturbed site features and other items plus provide all appurtenances to complete the work as shown on the Drawings and specified in the Contract Documents for a complete and ready-for-use installation. Any replacement or restoration of pavement necessary outside the pay limits specified on the contract drawings will be paid at the expense of the Contractor.

ITEM 12 –RESTORATION SEEDING & MULCHING

- A. Measurement: The quantity of each type of seeding and mulching measured for unit price payment purposes, will be the number of square yards of seeding and mulching acceptably placed and compacted when required or as specified over an area within the contract (pay) limits.
- B. Payment: The unit price stated in the Bid Schedule shall be full compensation for each square yard of seeding and mulching furnished and installed which is directly or indirectly caused by the project work as shown on the Drawings and/or specified in the Contract Documents for a complete and ready-for-use installation.

ITEM 13 –TEMPORARY HOLD UTILITY POLES

- A. Measurement: The quantity of each utility pole held during construction, will be each held when required or as specified.
- B. Payment: The unit price stated in the Bid Schedule shall be full compensation for each utility pole held during the installation of the proposed sanitary sewer s proposed by the project work as shown on the Drawings and/or specified in the Contract Documents.

THIS PAGE INTENTIONALLY LEFT BLANK

PROPOSAL TO THE CITY OF CLYDE, OHIO
WEST MAPLE STREET SANITARY SEWER EXTENSION

TO: MAYOR SCOTT BLACK
CITY OF CLYDE
222 NORTH MAIN STREET
CLYDE, OHIO 43410

Gentlemen:

Proposal of _____ (hereinafter called "BIDDER"), organized and existing under the laws of the State of Ohio doing business as _____.
To the CITY OF CLYDE (hereinafter called "Owner").

In compliance with your Advertisement for Bids, BIDDER hereby proposes to perform all WORK for the construction of the WEST MAPLE STREET SANITARY SEWER EXTENSION in strict accordance with the CONTRACT DOCUMENTS, within the time set forth therein, and at the prices stated below.

By submitting this BID, the BIDDER, or in the case of a joint BID, each party thereto, certifies as to its own organization, that this BID has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this BID with any other BIDDER or with any competitor.

The undersigned have full knowledge of the project site, Drawings, and the conditions of the proposal. The undersigned also, hereby agrees to furnish all the services, labor, materials and equipment necessary to complete these projects according to the Drawings and Specifications and to accept as full compensation the lump sum or unit prices stated in the Bid Schedule for the work and for use when calculating the price of a deduction or an increase in quantities.

BIDDER hereby agrees to commence WORK under this Contract on or before a date to be specified in the NOTICE TO PROCEED and to fully complete the PROJECT within the period stipulated in the INSTRUCTIONS TO BIDDERS. BIDDER further agrees to pay as liquidated damages and that the CITY may retain from monies that are, or which may become due. The amount of such liquidated damages shall be as stipulated in the CONTRACT AGREEMENT FORM (Section 00500 herein).

* Insert "a corporation", "a partnership", or "an individual" as applicable.

The Bidder hereby acknowledges receipt of the following addenda:

<u>ADDENDUM NO.</u>	<u>DATE</u>
<hr/>	<hr/>
<hr/>	<hr/>
<hr/>	<hr/>

We further agree that the Owner may reject any or all bids.

SUBMITTED BY:

Firm, Corporation or Individual

Address

Telephone Number

Contractor License Number

Signature:

 Date:

NOTE: Evidence of authority to sign and the corporate seal must be affixed and attested by the Secretary.

COMPLETION DATE: 60 Calendar Days commencing on the date as shown on Notice to Proceed for Final Completion.

PROPOSAL TO THE CITY OF CLYDE, OHIO
WEST MAPLE STREET SANITARY SEWER EXTENSION

BID SCHEDULE

Bid Item	Item Description	Est. Qty.	Unit	Unit Price Material	Unit Price Labor	Total Unit Price	Total Price
1	Bonds & Insurance	1	Lump Sum				
2	Mobilization	1	Lump Sum				
3	Maintenance of Traffic	1	Lump Sum				
4	12" PVC Sewer SDR 35	625	LF				
5	12" PVC Sewer SDR 35 (Premium Backfill)	1,175	LF				
6	Sanitary Manhole	7	Each				
7	6" PVC Sewer Lateral (Long)	8	Each				
8	6" PVC Sewer Lateral (Short)	7	Each				
9	Asphalt Drive Removal and Replacement	40	SY				
10	Gravel Drive Removal And Replacement	60	SY				
11	Type C Pavement Removal and Replacement	250	SY				
12	Restoration Seeding and Mulching	4000	SY				
13	Temporary Hold Utility Poles	2	Each				
TOTAL							

THIS IS AN UNOFFICIAL BID SHEET
FOR REFERENCE ONLY

TOTAL AMOUNT OF PROJECT (IN FIGURES)

TOTAL AMOUNT OF PROJECT (IN WORDS)

END OF SECTION

ADDENDUM #1

THIS PAGE INTENTIONALLY LEFT BLANK